

See discussions, stats, and author profiles for this publication at: <https://www.researchgate.net/publication/340593261>

THE CATASTROPHIC DECREASE OF PRESPA LAKE LEVEL – RESULT OF NATURAL OR ANTHROPOGENIC REASON? ПРИРОДНА ИЛИ АНТРОПОГЕННА Е ПРИЧИНАТА ЗА КАТАСТРОФАЛНОТО ПОНИЖАВАНЕ НА НИ....

Conference Paper · April 2020

CITATIONS

0

READS

177

3 authors, including:



Romeo Eftimi

84 PUBLICATIONS 401 CITATIONS

SEE PROFILE

Some of the authors of this publication are also working on these related projects:



ITMS 26220220002: Výskum dopadu klímatickej zmeny na dostupné množstvá podzemných vôd v SR a vytvorenie expertného GIS [View project](#)

THE CATASTROPHIC DECREASE OF PRESIPA LAKE LEVEL – RESULT OF NATURAL OR ANTHROPOGENIC REASON?

Prof. Dr Romeo Eftimi, eftimiromeo@gmail.com - Tirana, Albania

ПРИРОДНА ИЛИ АНТРОПОГЕННА Е ПРИЧИНАТА ЗА КАТАСТРОФАЛНОТО ПОНИЖАВАНЕ НА НИВОТО НА ПРЕСПАНСКОТО ЕЗЕРО

Проф. д-р Ромео Ефтими, eftimiromeo@gmail.com - Тирана, Албания

ABSTRACT

In southeaster Albania, on the border with North Macedonia and Greece, there are located the lakes Big Prespa (253.6 km²) and Small Prespa (47.4 km²). Both lakes are linked by a small channel with a sluice that separates the two lakes. The absolute mean level of Prespa Lake is considered 850 m above sea level (asl), and the maximal registered in 1993 lake is 852.91 m. During the period 1963-2003 a successive lowering of the lake level continued, with some interruption of this tendency during the period 1977-1986. The lowest level in 2003 was registered at 844.42 with cumulative amplitude for the period 1963-2003 of 8.29 m. Some specialists give the following hypothesis to explain the lake water decrease: a) increase of the transmissibility of the karst aquifer separating Prespa Lake from Ohrid Lake, and such intensifying the draining of the first lake to the second one; c) increase of the lake water use by the local population for agriculture and industrial purposes, and b) change of the climatic conditions in recent years.

However, the analyses of some meteorological and archaeological facts suggest that Prespa Lake level decrease is a consequence of the climatic conditions, which changes, in the past seems has been more intensive than today. The lake level lowering gave the possibility, also, some karst phenomenon of the lakeside, like the Zaver swallow hole, to be observed and described better.

KEYWORDS: Prespa Lake, karst aquifers, environmental impact, climatic changes

РЕЗЮМЕ

В югоизточна Албания, на границата със Северна Македония и Гърция, се намират Голямото (253,6 km²) и Малкото (47,4 km²) Преспанско езеро. Двете езера се свързват помежду си чрез един малък канал с шлюз. Средното ниво на Преспанското езеро е 850 m надморска височина, а максималното равнище от 852,91 m е регистрирано през 1993 г. В периода 1963-2003 г., с прекъсване през 1977-1986 г., е фиксирано последователно намаляване на нивото на езерото. Най-ниското регистрирано ниво е 844,42 m при обща кумулативна амплитуда 8,29 m за целия период 1963-2003 г. Изказват се следните хипотези за намаляване на нивото на езерото: а) увеличаване на хидравличната проводимост на карстовия водоносен хоризонт, разделящ Преспанското езеро от Охридското езеро, в резултат на което се усилва дрениране на първото езеро към второто; б) увеличаване на използването на водите на езерото от местното население за селскостопански и индустриални цели; в) изменение на климатичните условия през последните години. Проучването на метеорологичните и археоложките факти обаче показва, че понижаването на нивото на Преспанското езеро е следствие от промени в климатичните условия, които в миналото най-вероятно са били много по-интензивни от сега. Понижаването на нивото на езерото даде възможност да се изследват по-детайлно някои карстови феномени на езерото, като понорът Завер.

КЛЮЧОВИ ДУМИ: Преспанско езеро, карстов водоносен хоризонт, влияние на околната среда, климатични промени

Report delivered at the National Conference with International Participation „GEOSCIENCES 2019“, December 5-6, 2019, Sofia University „St. Kliment Ohridski“, Sofia. More information on the event on page 15

Доклад, изнесен на Национална конференция с международно участие „ГЕОНАУКИ 2019“, 5 - 6 декември 2019 г. Софийски университет „Св. Климент Охридски“, София. Повече информация за събитието на стр. 15



PROF. DR ROMEO EFTIMI Romeo Eftimi during the period 1963-1993 worked in Hydrogeological Enterprise where for more than 10 years has been chief hydrogeologist. He is specialized in Italy and in Austria for application of environmental isotope methods on groundwater investigations, which he applied in some very successful projects including the establishing the underground connection between Prespa and Ohrid Lake. He has the titles Professor and Doctor of sciences. He has a wide experience and has given a big contribution in fields of the hydrogeology of Albania. He is the leading author of Hydrogeological Map of Albania, scale 1:200.000, as well as of the Albania share of hydrogeological Map of Europe, scale 1:1.500.000, and of the World Map of Karst Aquifers and of the World Map of Transboundary Aquifers. He has published more than 60 papers, 4 university textbooks, and 3 monographs. He is a member of Karst Commission of International Association The last, and most important monograph is the „Thermal and Mineral Waters of Albania” published in 2016. He has participated in more than 35 International Conferences with original presentations. After 1993 he works as a private consultant for many national and international projects in the field of water supply and of environmental protection. Some important projects of this period are related to the water supply of many cities of the country like Korça, Pogradec, Shkodra, Laç, Durrës, Mamurras, Kavajë, Elbasan, Vlorë, Gjirokastra, Saranda etc. He is awarded with three Republican Prizes for excellent scientific results on hydrogeological investigation of Albania on 1969, 1979 and 1985. He is a member of the scientific board of the four international Journals: „AQUAmundi” Torino-Italy, Annales Géologiques de la Péninsule Balkanique Belgrad-Serbia, „Acta Geographica Silesiana” Sosnowiec-Poland and „Hidrogeologia and Inzhenerna Geologia” published by the Bulgarian Academy of Sciences.

INTRODUCTION

In South-eastern Albania, in bordering area with North Macedonia and Greece Prespa and Ohrid Lakes constitute a common hydraulic system. Prespa Lake has no surface flow and the outflow of the Lake is realized only through karst underground conduits into Ohrid Lake. During some decades Prespa Lake has suffered extremely worrying water level decline of about 8.5 m, which is seriously influenced by natural climatic changes as well as by uncontrolled anthropogenic impact. As a result of insufficient scientific collaboration the hydrology and hydrogeology of this wide and complicated watershed is not fully investigated. This paper will try to shortly analyze the problem and should bring some important field observation helping the discussion.

GEOLOGY

Mali Thate–Galichitsa Mountain consists mainly of Upper Triassic-Lower Jurassic (T_3-J_1) massive limestone with highest peak 2287 m above sea level (asl) (Fig. 1). During the Pliocene-Quaternary the study area embraced strong and progressive general uplifting, while the depression areas suffered mainly subsidence and partially uplifting (1). Most significant result of this tectonic style is the formation of big Mali Thate – Galichitsa Mountain horst. On both sides of the horst big graben structures are placed: Prespa Lake graben to the east, and Ohrid Lake and Korça plain grabens to the west. Some regional faults with north-south orientation are developed along the Eastern and Western edges of Mali Thate-Galichitsa horst. The Pliocene deposits represented by clay, sandstone and conglomerate fill most of the bottom of Prespa Lake and some small outcrops are developed along the lakeside.




Fig. 1. Simplified hydrogeological map of the area between Prespa and Ohrid lakes

HYDROGEOLOGY

Main hydrogeological features of the area are shown on **Fig. 1**. The elevation and the surface of Ohrid Lake are respectively 694 m asl and 348 km², while those of Prespa Lake are respectively 849 m asl and 274 km². Small Prespa Lake surface is 47.4 km² and the water level is 1 to 3 m higher than that of Big Prespa and a natural sandy dam with a sluice gate separates them. Ohrid and Prespa Lakes are separated by the karst massive of Mali Thate-Galichica Mountain characterised by dense presence of karst phenomena like karst plateaus, dead valleys, sink-holes and caves. As the Prespa Lake water level is about 150 m higher than that of Ohrid Lake, big karst water quantities flow through Mali Thate-Galichitsa karst massive to the Ohrid lakeside recharging many karst springs in the bordering area between Albania and North Macedonia. Main water recharges are the big springs of St. Naum average discharge 7.5 m³/s and that of Tushemisht with 2.5 m³/s. There are also two other groups of springs, Biljana near Ohrid with an average discharge between 1 and 2 m³/s and a group of springs, with total discharge of about 0.5 m³/s, issues in Devoll River Valley in Albanian territory, near the villages Golloborda, Manchurisht and Proger, in Devoll River Valley (2).

Jovan Cvijić (3) in 1905 described in detail the karst phenomenon of the Prespa and Ohrid lakes area and formulated the hypothesis that Prespa Lake recharges St Naum and Tushemisht springs issuing in Ohrid lakeside. Some investigations conducted with environmental isotope techniques supported by IAEA – Vienna have demonstrated that Tushemisht Spring at about 52-54%, and St. Naum Spring at about 42–46 % are recharged by Prespa Lake (4, 5, 6, 7, 8). However, the most significant and curious karst phenomenon of the area is Zaver swallow hole, which is located in Prespa lakeside between Small Gorica and Gollomboch villages (in Albanian territory). There an intensive loss of the lake water into the karst basin could be seen (**Fig. 2**). Taking into consideration the difference of water levels in both lakes of 155 m in average and the distance of 17 km between the two lakes in the direction Zaver swallow hole - Tushemisht and St. Naum, the maximum hydraulic gradient of karst water flow is 0.0091.



Fig. 2. Zaver swallow hole; photo of 12 September 2019

CATASTROPHIC DECREASE OF PRESPA LAKE LEVEL

Lake Prespa is an important natural, ecological and economical water resource in a region suffering water shortage **Fig. 3** and **4**. During the period 1963–2002 Prespa lake level is lowered 8.79 m, with a decreasing level trend of 21.7 cm/year, while the decreasing trend of the precipitation for the same period is 7.8 mm (6). During the period 1951–2000 Prespa Lake level is lowered 7.79 m, with the decreasing trend of 10.9 cm/year, and the precipitation decreasing trend, for the same period, of 3.16 mm/year (9). Both investigations take into consideration different time periods.

Many balance calculations of Prespa–Ohrid basin performed by different authors and institutions of three neighboring countries result in big discrepancies (6, 9, 10). This is the result of missing collaboration and coordination regarding exchange of documentations between the three countries and systematic measurements of important water points (springs, rivers etc) as well as regarding the measurements of the climatic elements at high elevation areas of the karst basin and lack of data of snow fall and evaporation. Mostly, the conclusions of the investigators about the Prespa Lake level decline are based only on the data of “own country”. In the specialized technical literature (6, 7, 9, 11), there are expressed different opinions about the Prespa Lake level decrease which could be summarized as (a) geological (tectonic and karst widening of underground channels connecting both lakes), (b) anthropogenic (intensive use of lake water for irrigation) and (c) less recognized climate changes).

The widening of the tectonic-karst pathways transmitting the water from Prespa Lake to Ohrid Lake presuppose at least the increase of the discharge of the big karst springs of Tushemisht and St Naum, which is not supported by some non systematic measurements of the discharge of the springs.

The anthropogenic impact on Prespa Lake level is related to the increased use of the Prespa Lake water for irrigation or for other purposes. Often the increased use of Prespa Lake is related mainly to the “intensive” use of the lake Small Prespa for irrigation in Albanian territory. In 1976 the Devoll River in Albanian territory was diverted to flow to Small Prespa Lake and during the period 1976–1996 the River input was about 30–70 million m³/year with the intention to be used for irrigation of Korça plain during the summer. As the constructed sedimentation basins of Devoll River didn't functioned normally about 40.000 m³, of fine grained sediments are deposited every year in Small Prespa Lake, which in total reach about 800.000 m³. The huge quantities of sediments changed completely the littoral zone and in the Albanian territory the beautiful Small Prespa was transformed into a wetland making impossible to further host the Devoll River water (**Fig. 5**). It is obvious that the lake water used for irrigation can't be the reason for the decrease of Big Prespa Lake level. The maximal volume of Prespa Lake in 1961 was 4.23 km³ which has so far decreased by about 1.1 km³ (9). The used for irrigation water quantity is relatively small comparing with the total volume of Big Prespa Lake and moreover the used for irrigation water



Fig. 3. Zaver Swallow hole; water level elevation at about 847 m asl (2012)



Fig. 4. Zaver Swallow hole; water level elevation at about 844.5 m asl (2005)

mostly was supplied by Devoll River belonging to another watershed.

Another anthropogenic impact on the decline of Prespa Lake level could be also the use of lake water for the massive irrigation of Resen plain located north to the Lake in the territory of North Macedonia, or the use of Small Prespa water for irrigation in Greek territory but no published data exist about these activities.

ZAVER SWALLOW HOLE AS A TESTIMONY OF THE CLIMATIC CHANGES

For a better understanding of the climate changes let us describe in more detail the Zaver swallow hole. This is the biggest and most important swallow hole where the water of Prespa Lake disappears to reappear in the big

karst springs along the Ohrid lakeside. The configuration of Zaver swallow hole at high water level is like a prolongation of the lake about 600 m in length finishing in a natural vertical Upper Triassic limestone wall about 25 m high of Mali Thate Mountain (Fig. 6). At the foot of the limestone wall is located Zaver swallow hole and a big cave not yet well investigated is developed close to it. In the memory of the local people is transmitted the description of a “road” connecting two sides of the Lake prolongation finishing to Zaver swallow hole but no one has seen it until the years 2002–2005. At this time interval the Lake arrived the lowest known level of about 844.5 m asl and the road emerged with all its mystery. The road is about 200 m long; it is constructed like a dam which the carriage way in average about 2.5 to 3.0 m wide, while its height varies from about 0.5 m in both extremes of the road to about 3 m in the central, deepest part of the water flowing to Zaver swallow hole. The road is constructed



Fig. 5. The littoral zone of Lake Small Prespa in Albanian territory is transformed into a wetland by the sedimentation of the small-size sediments of Devoll river diverted into the lake



Fig. 6. During 2005 was possible to see the presence of a road (or dam) connecting two sides of the Prespa Lake prolongation finishing in Zaver swallow hole




Fig. 7. The “road” is constructed with stones of different dimensions and without pavement and is much more similar to a dam

with stones of different dimensions, from about 15–20 cm to big blocks more than 70–80 cm thrown without order and actually no signs of any former pavement could be seen on the road. The used building stones are taken from the local sandstone-conglomerate Pliocene deposits outcropping along the lakeside near Zaver swallow hole and consist of igneous, metamorphic and carbonate rocks (Fig. 7).

The presence of the road suggests some questions. When and why is constructed this “road”? Is there an ancient “road” or an ancient “dam”? Why was necessary to construct this “road”? About the time of the construction of the road there is no any testimony; the local people say that “the road is very old and no one knows when it was constructed”. The stone road is shorter and more convenient comparing with the former existing road passing on limestone rocks and quite near to Zaver swallow hole. At the actual situation the stone road is not convenient and is not used by the local population. The water level on both sides of the road is different; the level of the Prespa Lake is about 0.8 m higher that of flowing water to Zaver swallow hole. May be the road is a dam constructed to keep Lake level at higher elevation so important for the fishing activity of the local people.

The construction of such a road (or dam) is justified only if for a long time (at least some tens of years or more) in the past Lake Prespa level has suffered by climatic shortages similar to the actual ones. An important investigation undertaken to explain the past climatic variability determining the sediment isotope and geochemical record from Lake Prespa over the Last Glacial cycle found very low lake levels occur around 1000 years ago and a rapid reversal is established in the last 500 years (12). This period could be the age of the road of Zaver swallow hole as well.

CONCLUSIONS

The existence of the ancient road of Zaver swallow hole testify that the main reason of the extraordinary decline of Prespa Lake water level are the permanent cyclic climate shortages on which nowadays overlap seriously the dangerous anthropogenic impacts as well.

REFERENCES

1. Aliaj, Sh. 2012. Neotectonic of Albania. Tirana, KLEAN, 292 p. (in Albanian).
2. Eftimi R, Bisha G, Tafilaj I, Sheganaku Xh 1985. Hydrogeological map o Albania, scale 1:200.000, Tirana
3. Cvijic J, 1906: Fundamentals of Geography and Geology of Macedonia and Serbia, Special Edition, VIII+680, Belgrade (in Serb-Croat.).
4. Anovski, T., B. Andonovski, B. Minceva. 1991. Study of the hydrologic relationship between Ohrid and Prespa lakes. – In: Proceedings of an IAEA International Symposium, 11–15 March 1991 Vienna, IAEA-SM-319, p. 62.
5. Eftimi, R., J. Zoto. 1997. Isotope study of the connection of Ohrid and Prespa Lakes. – In: Proceedings of International Symposium “Towards Integrated Conservation and Sustainable Development of Transboundary Macro and Micro Prespa Lakes”. Korcha, Albania, 24–26 October 1997, 32–37.
6. Kolaneci, M. 2003. IAEA Regional project RER/8/008 Study of Prespa Lake using nuclear and related techniques
7. Matzinger, A, M. Jordanoski, E. Veljanoska-Sarafiloska, M. Sturm, B. Müller, A. Wüest. 2006. Is Lake Prespa jeopardizing the ecosystem of ancient Lake Ohrid? – *Hydrobiologia*, 553, 89–109.
8. Eftimi R, Amataj S, Zoto J. 2007. Groundwater circulation in two transboundary carbonate aquifers of Albania; their vulnerability and protection. In: Witkowski Aj, Kowalczyk, Vrba J. (Eds). *Groundwater Vulnerability Assessment and Mapping*, vol. II, Taylor & Francis, The Netherlands, pp. 206–218
9. Popovska, C., O. Bonacci. 2007. Basic data on the hydrology of Lakes Ohrid and Prespa. – *Hydrological Processes*, 21, 5, 658–664.
10. Pano, N. 1984. *Hydrology of Albania*. Tirana, Institute of Hydrometeorology, Academy of Science, 441 p. (in Albanian).
11. Hollis G.E. & Stevenson A. 1997. The physical basis of the lake Mikri Prespa system: geology, climate, hydrology and water quality. *Hydrobiologia* , 351, 1, 1–19.
12. Leng, M. J, B. Wagner, A. Bohem, K. Panagiotopoulos, C. H. Vane, A. Snelling, C. Haidon, E. Woodly, H. Vogel, G. Zancheta, I. Baneschi. 2013. Understanding past climatic and hydrological variability in the Mediterranean from Lake Prespa sediment isotope and geochemical record over the Last Glacial cycle. – *Quaternary Science Reviews*, 66, 123–136.